

WILSON SUPER X

Technical Information

Model number	WILSON SUPER X
Rated output (415V)	13.0 kW
Rated current (415V)	18 Amp
Phases	3 phase
Electrical installation	As per AS/NZS3000
Installation requirements	AS/NZS3500.4.2 & local requirements
Switch on flow rate	4.5 L/min = 40°C temperature rise
Permissible operating pressure	1050 kPa
Temperature adjustment	N/A
IP Rating	IP24
Height	220mm
Width	350mm
Depth	130mm
Colour	white
Nominal capacity	0.5L
Flow rate limiter (if fitted) L/min	5L/min
Equipment	
Heating system	Copper Tubular
Electronic air detection system	-
Domestic Warranty*	2 years

MPG RECOMMENDATION – UPGRADE TO DHB-13E

Wilson Super X	DHB-13E
2 year warranty	5 year warranty
4.5L per minute flow rate. If less than 4.5L of hot water are used per minute the unit will switch off. A common complaint from customers is that water temperatures fluctuates.	3L per min flow rate Better flow rate per minute, only three (3) litres of water use per minute required for unit to engage.
Not temperature controlled	Temperature controlled

If you would like to see a DHB-13 in operation in a showroom or to get a free quote please call **1800 MACKIE (1800 622 543)**

Mackie Plumbing and Gas Pty Ltd
PO Box 1493, South Perth, 6915, Western Australia
Tel: 1800 MACKIE (622 543)
Email: reception@mackieplumbingperth.com.au

Registered in Australia: ABN: 29 168 696 204
Plumbing & Gas Licence: PL8621 / GS015660

